

Annual Operation Plan

Name of U.B: Gazipur City Corporation (GCC)

Financial Year: 2023-2024

Subject Asset			Work Specification				Management	
1 ID No.	2 Name	3 Asset Type	4 Item	5 Volume of Work / Input	6 Cum	7 Estimated Cost (Lakh Taka)	8 Source of Fund	9 Responsible Section
ICGP B2 GCC-05(b)	b) Construction of RCC drain at Kashimpur to Streepur connecting road (Zilernoor to Mother textile) (Ch.0+000 to 4+500) & Link	Drain	Drain Cleaning	2858.28	Cum	34.45	GCC Own	Engineering Section
ICGP B2 GCC-13	Construction of drain along the side of Nowzour to Zirani Bazar (starting from Zilernoor to west direction up to 6.75 Km). (Ch. 00+000 to 6+750)	Drain	Drain Cleaning	3582.123	Cum	43.18	GCC Own	Engineering Section
ICGP B2 GCC-18	Construction of RCC drain (BADC mor to Mother Textile) from Mission gate to Nager Hanoi Jora Bridge. Ch.0+000 to 1+250	Drain	Drain Cleaning	2866.250	Cum	32.14	GCC Own	Engineering Section
ICGP B1 GCC-15	RCC Drain Cleaning from Gacha Road (Fokir Market) to Hazi Abdul Latif Primary School & Link Road. Ch.0+000 to 757	Drain	Drain Cleaning	787	m	2.01	GCC Own	Engineering Section
ICGP B1 GCC-02	Construction of RCC drain along the side of Maleker bari road (Dhaka Mymansingh Highway) to Bashan sarak Via Ozarpara & Haque Market and Link Ch.00 to 2+305.	Drain	Drain Cleaning	2305	m	5.88	GCC Own	Engineering Section

[Handwritten Signature]

[Handwritten Signature]

ICGP B2 GCC-14:	Installation of 1 (One) Nos production Tube wells, Pumps house, Necessary electrical work with 10.00 km distribution tube pipe line at Zone-02 respectively.	WSS	Pump operational cost	Per month	month	.04	GCC Own	Engineering Section
ICGP B2 GCC-22	Repairing of road by Rcc Road from Simtokoil to Naga Bridge.	Drain	Drain Cleaning Disposing surplus excavated soils of all types outside the site premises up to a lead of specified distance including cost of labor, cost of equipment etc. Manhole cover	444,000 355,200	Cum	6.34	GCC Own	Engineering Section
ICGP B1 GCC04	Construction of Drain (RCC/Pipe) along the side of the road from Rajendrapur BRAC center gate to MirzapurBazar canal	Drain	Drain Cleaning	8100	Cum	97.633	GCC Own	Engineering Section

Prepared by
Date:

15.12.24
Sohrab Hossain
Sub-Assistant Engineer
Gazipur City Corporation

MD. MYDULISLAM
Executive Engineer (CMT)
Zone-4
Gazipur City Corporation.

Approved by
Date:

এ কে এম হাবিবুর রহমান
(উপায়ুক্ত অফিসার) (ড: গা:)
গাজীপুর সিটি কর্পোরেশন
গাজীপুর।

শ্রীঃ আকবর হোসেন
অতিরিক্ত অথন অফিসার
গাজীপুর সিটি কর্পোরেশন
গাজীপুর।

শ্রীঃ আমিনুল ইসলাম
অথন অফিসার
গাজীপুর সিটি কর্পোরেশন, গাজীপুর।

Annual Maintenance Plan

Name of ULB: Gazipur City Corporation (GCC)

Financial Year: 2023-2024

Subject Asset					Work Specification			Schedule			Management			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
ID No.	Name	Asset Type	Present Condition	Type of Work	Detail of Work	Location/Chain age From - To (km)	Required Work Volume (unit)	Estimat ed Cost (Lakh Takā)	Work Start from (dd/mm/yyyy)	Work End at (dd/mm/yyyy)	Priority Rank	Source of Fund	Responsible Section	
ICGP B2 GCC-04R	Repairing & Widening of Tongi Vadam road by RCC work with pipe drain and Link road.	Road & Drain	Poor	Emergency	Earth Filling, Tack coat, wearing coarse, inspection pit wall up, Top slab, manhole cover etc.	Ch. 0.0-2900.0 (Various location)	EFW(CE): 600 TCHD: 17690 25mmDC: 17690 BW (1:4): 48.138 RCC-30SCCM: 65.088 Deformed Bar: 9713.480 Manhole cover: 58 etc.....	Cum Sqm Sqm Cum Cum Kg No's	174.0	01/12/2023	30/05/2024	1	GCC Own	Engineering Section
ICGP B2 GCC-10 & ICGP B2 GCC-11R	Repairing & widening of Khapara road (starting from Dhaka - Myrmensingh road to Vadam road via Tliargati) (Ch-0+00 to Ch-3+810) By RCC Work & Construction of RCC Drain along side of Khapara road last part (up to Tliargati road) Ch. 1+375 to Ch-3+810	Road & Drain	Poor	Routine Repair	Box cutting, sand filling, sub base, tac-coat, wearing coarse, RCC work etc.	Ch. 0.0-2000.0 (Various location)	BC&SGC(450mm: 112 Sand Filling: 49.576 SBBC: 21.0 TCHD: 14000.0 25mmDC: 14000.0 RCC-30SCBP: 22.5 SBFS: 33.750 BW (1:4): 5.1 Earth work: 53.760 RCC-30SCCM: 34.5 Deformed Bar: 6934.920 etc.....	Sqm Cum Cum Sqm Sqm Cum Cum Sqm Cum Cum Cum Kg	123.05	01/12/2023	30/05/2024	2	GCC Own	Engineering Section

ICGP B2 GCC-05(a)	a) Repairing & Widening of BC Road from Kashimpur to Streepur connecting road (UP to Mother Textile); (RCC Road Ch. 0+000-4+500)(Link-1 BC Road Ch.0+380-1+277.7) and 530m link-2 RCC road with side drain (Engineer bar road starting from Gachha polasona main road)	Road	Poor	Emergency	Earth work, sand filling, sub base, WBMB/C, PCC, Brick work, RCC work etc.	Ch. 0.0-4400.0 (Various location)	Earth work: 15.12 Sand Filling: 72.198 SBBC: 69.048 WBMB/C: 122.444 PCC: 2.363 BW(1.4): 9.45 RCC-25SCBP: 92.064 Deformed Bar: 467.4551 etc.....	Cum Cum Cum Cum Cum Cum Kg	38.939	01/12/2023	30/05/2024	03	GCC Own	Engineering Section
ICGP B2 GCC-05(b)	b) Construction of RCC drain at Kashimpur to Streepur connecting road (Zitermour to Mother textile) (Ch.0+000 to 4+500) & Link	Drain	Poor	Routine repair	Drain top slab casting, RCC work.	Ch. 0.0-4400.0 (Various location)	RCC-25SCCM: 32.94 Deformed Bar: 3572.76 Etc.....	Cum Kg	12.83	01/12/2023	30/05/2024	04	GCC Own	Engineering Section
ICGP B2 GCC-13	Construction of drain along the side of Nowzour to Zitrani Bazar (starting from Zitermour to west direction up to 6.75 Km). (Ch. 00+000 to 6+750)	Drain	Poor	Routine repair	Drain top slab casting, RCC work.	Ch. 0.0-6850.0 (Various location)	RCC-25SCCM: 38.43 Deformed Bar: 4168.22 Etc.....	Cum Kg	14.96	01/12/2023	30/05/2024	05	GCC Own	Engineering Section
ICGP B2 GCC-18	Construction of RCC drain (BAD/C mor to Mother Textile) from Mission gate to Nager Halot Jora Bridge. Ch.0+000 to 1+250	Drain	Poor	Routine repair	Drain top slab casting, RCC work.	Ch.0+000 to 1+250 (Various location)	RCC-25SCCM: 7.444 Deformed Bar: 1366.4 Etc.....	Cum Kg	3.77	01/12/2023	30/05/2024	06	GCC Own	Engineering Section

[Handwritten signature]

[Handwritten signature]

ICGP B2 GCC 08R	Repairing and widening of road from Surabari Rice mill to Kashimpur-Sreepur Road Kazi Market Mr.Malek House via Shalidubi Member Market. (RCC Part)	Road	Poor	Emergency	Earth work, sand filling, sub base, WBMBC, PCC, Brick work, RCC work etc.....	Ch. 0.0-1850.0 (Various location)	Earth work: 30.24 Sand Filling: 65.82 SBBC: 40.32 WBMBC: 71.5 PCC: 4.732 BW(1:4): 18.9 RCC-25SCBP: 53.76 Deformed Bar: 2735.04 etc.....	Cum Cum Cum Cum Cum Cum Kg	25.05	01/12/2023	30/05/2024	07	GCC Own	Engineering Section
ICGP B2 GCC 08R	Repairing and widening of road from Surabari Rice mill to Kashimpur-Sreepur Road Kazi Market Mr.Malek House via Shalidubi Member Market. (BC Part)	Road	Poor	Emergency	Earth filling, sand filling, End Edging, sub base, Base coarse, wearing coarse, etc.	Ch. 0.0-2725.0 (Various location)	EFW(Dr): 270 Sand Filling: 128.0 SBBC: 120.0 WBMBC: 212.8 TCHD: 800.0 DCPM: 48.0 etc.....	Cum Cum Cum Cum Sqm Cum	40.85	01/12/2023	30/05/2024	08	GCC Own	Engineering Section
ICGP B2 GCC-12R	Repairing & Widening of road from Nowzour to Zitrani Bazar (starting from Zitermour to west direction up to 6.85. Km). (Ch. 0+00 to 6+850)	Road	Poor	Routine Repair	Earth work, sand filling, sub base, WBMBC, PCC, Brick work, RCC work etc.....	Ch. 0.0-4450.0 (Various location)	Earth work: 21.6 Sand Filling: 154.56 SBBC: 109.8 WBMBC: 194.711 PCC: 3.375 BW(1:4): 13.5 RCC-25SCBP: 146.4 Deformed Bar: 7374.84 etc.....	Cum Cum Cum Cum Cum Cum Kg	73.26	01/12/2023	30/05/2024	09	GCC Own	Engineering Section
ICGP B2 GCC-21 & ICGP B2 GCC-23(c)	a) Improvement of BC road from Mosher market to Kaler Vlia mosque via Magjal Mosque.	Road	Poor	Routine Repair	Earth filling, sand filling, End Edging, sub base, Base coarse, wearing coarse, palisading work etc....	(Various location)	EFW(CE): 257.150 Sand Filling: 118.30 SBBC: 88.725 EE(75mm): 660.0 S&SBC: 157.339	Cum Cum Cum m Cum	36.23	01/12/2023	30/05/2024	10	GCC Own	Engineering Section

[Handwritten signature]


[Handwritten signature]

						TCMD@.75: 921 EFW(CE) 64.50 etc.....	Sqm Cum											
ICGP B2 GCC-24	Repairing of BC from Malekerbari (Dhaka- Mymensingh) Road to Bason Chourasta & Link Road.	Road	Poor	Routine Repair	TCMD@0.75 DCPM	Ch. 0.0-2800.0 (Various location)	TCMD@0.75: 12692.500 DCPM: 634.625	Sqm Cum	181.76	01/12/2023	30/05/2024	13	GCC Own	Engineering Section				
ICGP B2 GCC-06	RCC Repairing by BC from Dhaka- Mymensingh Road to Bogar Tek Bridge at Joy Bangla Road.	Road	Poor	Routine Repair	TCMD@0.75 DCPM	Ch. 0.0-1800.0 (Various location)	TCMD@0.75: 8352.000 DCPM : 417.600	Sqm Cum	119.06	01/12/2023	30/05/2024	14	GCC Own	Engineering Section				
ICGP B1 GCC-15	RCC Road Repairing by Seal Coat from Gacha Road (Fokir Market) to Hazi Abdul Latif Primary School & Link Road.	Road	Poor	Routine Repair	TCMD@0.75 DCPM	Ch. 0.0-552.0 (Various location)	TCMD@0.75: 2776.72 DCPM : 138.836	Sqm Cum	39.76	01/12/2023	30/05/2024	15	GCC Own	Engineering Section				
ICGP B2 GCC-27	Repairing of road by BC & HBB start from Vannu to Dakhin Khan Gopalishna Mazhar Via Nagar Bhaban & Dirastram bazar.	Road	Poor	Routine Repair	EE(125mm): S&SBC(WG): CWB(M)(SSM): PCMD@1.2: TCHD@0.75: DCPM: HBPMM:	Ch. 4+552.0 (Various location)	EE(125mm): 1314.00 S&SBC(WG): 1172.370 CWB(M)(SSM): 881.474 PCMD@1.2: 5786.456 TCHD@0.75: 13612.971 DCPM: 544.456 HBPMM: 6602.286	M Cum Cum Sqm Cum Sqm	202.07	01/12/2023	30/05/2024	16	GCC Own	Engineering Section				
ICGP B2 GCC 08R	Improvement of Road By BC AT Sibbari Brt Office To East Direction Omeda Khatun School via Rajbari Dhal,Zourpukurper, Barack meagr Culvert	Road	Poor	Routine Repair	Box Cutting, sand filling, sub-base, base course, wearing course etc....	Ch. 3+625.0 (Various location)	Sand (FM 0.80) filling : 545.620 BC&SGC(450mm):1364.05 SBBC(FM-0.5): 341.013 S&SBC(WG): 1135.478 CWB(M)(SSM): 853.743 PCMD@1.2: 3414.970 BMPM: 827.003 TCHD@0.75:9661.620 DCPM: 1599.905 RMP(BY-TPO): 665.600 HBPMM: 2050.920	Cum Sqm Cum Cum Cum Sqm Cum Sqm Cum Sqm	594.98	01/12/2023	30/05/2024	17	GCC Own	Engineering Section				


[Handwritten signature]


[Handwritten signature]

ICGP B1 GCC05R	Repairing & Widening of road by BC from Blashtpur Bot Tola to Porabari Bazar of Dhaka- Maytensingh road to via Salna Bazar & Jolarpar Bazar (Blashtpur Botola to Salna Bazar to Jolarpar Bazar to Porabari Bazar	Road	Poor	Routine Repair	Box Cutting, sand filling, sub-base, base course, wearing course, palisading work etc....	TCMD@0.75: 22892.487 BCSSGP(450mm): 2025.2 Sand (FM 0.80) : 810.080 SBBC(FM<0.5): 405.040 EE(125mm): 664.000 WMBBC: 673.380 CWB(M(SSM)): 506.300 PCHD@1.2: 3416 DCPM: 121.512 EFM(CE): 582.66 Earth work : 2.16 PS: 120.00 Deformed Bar: 1262.736	Sqm Sqm Cum Cum Cum Sqm Cum Cum Cum Sqm Kg	132.77	01/12/2023	30/05/2024	18	GCC Own	Engineering Section
ICGP B1 GCC04	Construction Of Drain (RCC / Pipe) along the side of the road from Rajendrapur BRAC center gate to Mirzapur Bazar Cannel	Drain	Poor	Routine Repair	Drain top slab casting, RCC work.	RCC-25SCCM: 18.75 Deformed Bar: 874.65	Cum Kg	5.25	01/12/2023	30/05/2024	19	GCC Own	Engineering Section

Prepared by: 
Date: 15.02.24

Sohrab Hossain
Sub-Assistant Engineer
Gazipur City Corporation



M.D. MUBTISLAM
Executive Engineer (CMA)
Zone-4
Gazipur City Corporation.

App. by: 
Date: 24/02/24

এ কে এম হারুন রশীদ
তত্ত্বাবধায়ক প্রকৌশলী (চ: মা:)
গাজীপুর সিটি কর্পোরেশন
গাজীপুর।



গাজীপুর সিটি কর্পোরেশন
কোম্পিউটার অফিস প্রকৌশলী
গাজীপুর সিটি কর্পোরেশন
গাজীপুর।


স্বাক্ষর
গাজীপুর সিটি কর্পোরেশন
কোম্পিউটার অফিস প্রকৌশলী
গাজীপুর।